

Piling Industry Canada

PIC magazine

www.pilingindustrycanada.com

ISSUE 2 • 2015

The Hub

Trevi Hong Kong works on the
Hong Kong Boundary Crossing Facilities

Sky View

Downtown Miami
gets iconic new tower



Piling Industry Canada

PIC
magazine

www.pilingindustrycanada.com

In this issue

Piling Industry News **6**

Sky View – Downtown Miami gets iconic new tower and breaks a world piling record **14**

Performance Piling – New Children's Hospital of Saskatchewan puts piling to the test **18**

Tall Timbers – The University of British Columbia is set to build Canada's tallest wooden building **20**

Patented Sonic Pile – Anchors Set to Revolutionize Building Foundations **24**

The Hub – Trevi Hong Kong works on the Hong Kong Boundary Crossing Facilities **28**

No Substitute for Hard Work and Dedication – Davide Trevisani takes home DFI's DaVinci Legends Award **32**

LRFD versus ASD for Driven Piles – The code drives the methodology **36**

Design-Build – Optimizing value and foundations in the commercial, infrastructure, and industrial markets **38**

Stir It Up – ABI rigs utilized in soil mixing **42**

A Level Playing Field? – Not necessarily so for telescopic boom crawler crane design and lifting performance **44**

Money 101 – Improving your financial literacy can improve your business **48**

Index to Advertisers **49**

Free Directory Listing Form **50**

Published by
DEL Communications Inc.
Suite 300, 6 Roslyn Road
Winnipeg, Manitoba
Canada R3L 0G5

President & CEO: *David Langstaff*

Publisher: *Jason Stefanik*

Managing Editor: *Carly Peters*
carlypeters@mts.net

Sales Manager: *Dayna Oulian*
dayna@delcommunications.com

Advertising Account Executives:
Jennifer Hebert
Michelle Raikie

Production services provided by:
S.G. Bennett Marketing Services
www.sgbennett.com

Art Director/Design: *Kathy Cable*

Advertising Art: *Sheri Kidd,*
Joel Gunter, Dana Jensen

© Copyright 2015, DEL Communications Inc.
All rights reserved. The contents of this publication may not be reproduced by any means, in whole or in part, without prior written consent of the publisher.

While every effort has been made to ensure the accuracy of the information contained herein and the reliability of the source, the publisher in no way guarantees nor warrants the information and is not responsible for errors, omissions or statements made by advertisers. Opinions and recommendations made by contributors or advertisers are not necessarily those of the publisher, its directors, officers or employees.

Publications mail agreement #40934510
Return undeliverable
Canadian addresses to:
DEL Communications Inc.
Suite 300, 6 Roslyn Road
Winnipeg, Manitoba, Canada R3L 0G5
Email: david@delcommunications.com

Printed in Canada 12/2015

COVER PHOTO: Trevi Hong Kong Helps Stabilize Island

At the center of the Hong Kong-Zhuhai-Macao bridge project is a 150-hectare artificial island built to act as a transportation hub with clearance facilities for goods and passengers. Ground-strengthening measures were needed to stabilize the island's soft marine mud before facilities could be constructed.

Trevi Hong Kong installed 450 jet grout columns in a key area of the island, using six Soilmecc PSM-20 hydraulic drilling rigs, one Soilmecc 7T-505 and five Soilmecc 7T-600J high pressure pumps. The Soilmecc equipment performed flawlessly, helping Trevi Hong Kong maintain an aggressive production schedule to complete the project ahead of schedule.

Trevi Builds with Soilmecc.

For more information, contact Soilmecc North America:

Marco Chiarabelli, Corporate Sales Area Manager | 401.965.2575 | m.chiarabelli@soilmecc.it

soilmecc
north america



SoilmeccNA.com



The Hub

Trevi Hong Kong works on the Hong Kong Boundary Crossing Facilities

By Claudio Borgatti, operations manager at Trevi S.p.A., and Marco Chiarabelli, corporate sales manager for Soilmec North America

Three major cities in China – Hong Kong, Macau, and Zhuhai – will soon be connected by a series of bridges, tunnels, link roads, and boundary crossing facilities, providing a new direct link between the east and west banks of the Pearl River Delta for passenger and freight land transportation. At the expected cost of approximately US \$10.6 billion, the construction of the massive Hong Kong-Zhuhai-Macao Bridge project began in December 2009 and its completion is planned for late 2016. However, it faces daunting challenges as they combat nature to build and stabilize an artificial island that is central to the project.

A major project component is the Hong Kong Boundary Crossing Facilities (HK-BCF) that will serve as a transportation hub and provide clearance facilities for goods and passengers using the bridge. The HK-BCF is located on a 150-hectare artificial island that was reclaimed from open waters just northeast of the Hong Kong In-

ternational Airport. The landing points for the link roads and tunnels will utilize 20 hectares of the island. The remaining 130 hectares will be used for the HKBCF cargo, passenger, and vehicle inspection facilities; offices for the immigration, customs, and excise departments; road networks; and a public transport interchange and traffic control surveillance system.

The artificial island's sea wall was built using a new, non-dredge approach. Large 30-meter-diameter steel caissons were dropped into the sea a few meters apart and joined by a flexible steel wall. As the mud was dug out from the middle, each 450-tonne caisson drove itself down towards the hard strata. This new reclamation technique was used instead of the conventional approach of dredging out the soft mud down to the bedrock and replacing it with marine sand.

Additional ground strengthening measures were also needed to help stabilize the island's soft marine mud before construct-

ing boundary crossing facilities and tunnel landing points. Trevi Hong Kong joined these stabilization efforts by installing jet grout columns in a key area of the island.

STABILIZING WITH JET GROUTING

Trevi Hong Kong installed 450 jet grout columns with diameters ranging from 1.2 metres to three metres to a depth up to 35 metres. The jet grouting was performed by drilling a hole to the required depth, followed by rotating and extracting the drill rod while simultaneously pumping high-pressure fluid through nozzles at the foot of the drill string. A combination of air and cement grout slurry was injected as the breaking-up and consolidation agents, using the TREVIJET T1/S bi-fluid system. Five Soilmec 7T-600J high pressure pumps with four-inch pistons were used to install the large-diameter grout columns and a single Soilmec 7T-505 pump was used for the small-diameter columns.

Six Soilmec PSM-20 hydraulic drilling



Above: Constructing jet grout columns on an island had its unique challenges, including needing four barges to deliver cement from the factory in China to the jobsite.

Right: Trevi Hong Kong complete the jet grouting construction in only two months, thanks in part to the reliability of their six Soilmec drilling rigs.



rigs were deployed for this jet grouting construction. The drilling rigs were all equipped with a monitoring system that displayed on a built-in LCD screen and recorded on a dedicated memory disk the main drilling and jetting parameters, including depth, drilling rate, string revolution speed, drilling torque, grout pressure, grout and air flow rate, drilling and jetting time, column deviation, and x and y inclination.

The artificial island's geological conditions challenged the stabilization efforts. The top ground layer of about 8.5 metres of sand fill is followed by approximately 18.5 metres of very soft marine mud. Trevi Hong Kong needed to penetrate through the soft sand fill and marine mud into at least one metre of the Alluvium material that rests below.

The Soilmec drilling rigs performed beautifully, helping Trevi Hong Kong maintain an aggressive production schedule of at least eight jet grout columns per day.



Soilmec PSM-20 rigs jet grouting on an artificial island just northeast of Hong Kong International Airport.

SUPPLYING AN ISLAND

Trevi Hong Kong performed the jet grouting on a very tight schedule within 2.5 months. This translated into a demanding schedule for supply delivery to the island, given the required high rate of cement consumption.

Trevi Hong Kong used four barges with a capacity of 1,200 tonnes to transport cement from a factory in China to the jobsite on the island in order to prevent any interruption or delay in cement supply. Two additional barges were equipped with 14 horizontal silos, each with a capacity of up to 600 tonnes of cement, and four grout mixing plants. Sea water was used as the water source for drilling and mixing the cement grout. Given this setup, Trevi was able to produce up to 1,200 cubic meters of cement grout per day.

Trevi Hong Kong was awarded the sub-contract for the jet grouting in the middle of March 2015, and the work was successfully completed ahead of schedule on June 15, 2015. Trevi's speedy construction of the jet grout columns was greatly appreciated by their client, the main contractor. ●



Trevi Hong Kong depended on Soilmec drilling rigs to install 450 jet grout columns, helping to stabilize an artificial island at the centre of the Hong Kong-Zhuhai-Macao Bridge project.



Parked alongside the island, two barges were equipped with 14 silos and four grout mixing plants to keep up with the high consumption rate of cement grout – 1,200 cubic metres per day.